# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT54134

## APPROVED SCHEDULE - B

**No.EE/BTP/BBMP/E-PMT/18/2022-23, Date: 04-11-2022**

**Name of Work:Improvements and maintenance of Foothpath in ward No. 08 Jakkru.**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of BANGALORE PONNUSWAMY SHANMUGAM ( ) | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 279 | Removing and resetting of footpath slab | Sqm | 200.0 | Rupees Two Hundred Only |
| 2 | 303.84 | Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. | Cum | 180.0 | Rupees One Hundred Eighty Only |
| 3 | 27.39 | Providing and laying in position plain cement concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. | Cum | 5000.0 | Rupees Five Thousand Only |
| 4 | 52.29 | Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately) | Cum | 6000.0 | Rupees Six Thousand Only |
| 5 | 3.14 | Supplying, Fitting and Placing TMT Fe550 bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications. | tonne | 80000.0 | Rupees Eighty Thousand Only |
| 6 | 428.4 | Providing and Fixing pre cast covering Slab 100mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge. | Sqm | 1600.0 | Rupees One Thousand Six Hundred Only |
| 7 | 9.3 | Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paidseparately) Mix 1:2:4 (M15) Using 20 mm nominal size graded crushed coarse aggregates | Cum | 5797.83 | Rupees Five Thousand Seven Hundred Ninety Seven and Eighty Three Paise Only |
| 8 | 1034 | Providing and fixing pre cast solid cement concrete Kerb Stones made out of M20 with top and bottom width 114 and 165mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading, unloading, lead and lift transportion etc., complete as directed by the Engineer in charge of the work(from finish concrete and no painting to be done) | m | 380.0 | Rupees Three Hundred Eighty Only |
| 9 | 162.75 | Painting Two Coats on New Concrete Surfaces Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concretesurfaces. | Sqm | 80.0 | Rupees Eighty Only |
| 10 | 303.84 | Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3) | Cum | 102.0 | Rupees One Hundred Two Only |
| 11 | 388.92 | Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km | t.Km | 95.0 | Rupees Ninety Five Only |

B. P. Shayan

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore-92

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಡರಹಳ್ಳಿ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು